

## HASSAN DIVISION.

## ADVERTISEMENT.

*The 27th May 1892.*

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 19th June 1892, for constructing an additional block of building for Police and Forest Officers at Hassan. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1893.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing an additional block of building for Police and Forest Officers at Hassan; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of Work.	Per.	Quantity.	Total.
Excavating foundations .. .. .	C. Yd.	159	
Burnt brick in chunam .. .. .	C. Ft.	17,962	
Archwork in do .. .. .	Do	526	
Burnt stones slabs dressed .. .. .	S. Ft.	375	
Plastering with mortar .. .. .	Sqr.	172.92	
Color washing, 2 coats .. .. .	Do	47.92	
White washing do .. .. .	Do	125.00	
Flooring with Mangalore tiles .. .. .	C. Ft.	6.30	
Do with concrete and plastered over .. .. .	Sqr.	22.29	
Matting with thin rind bamboos .. .. .	Do	23.96	
Flat terracing 9" thick .. .. .	Do	36.41	
Wood work teak wrought and put up .. .. .	C. Ft.	439	
Teak wood doors with $\frac{1}{2}$ glazed & $\frac{1}{2}$ pannelled shutters and frames 4 x 7 .. .. .	S. Ft.	506	
Teakwood windows with pannelled shutters outside and glazed shutters inside with iron bars 1" diameter and swinging lights from above, &c. 3 x 4 $\frac{1}{2}$ .. .. .	Do	307	
Do ventilators with glazed shutters and frames .. .. .	Each.	16	
Wood oiling .. .. .	Sqr.	45.00	
Painting windows, &c. .. .. .	Do	12.50	
White ant composition .. .. .	Do	20.00	
Cornice, ornamental .. .. .	R Ft.	414	
Do ordinary .. .. .	Do	174	
Chunam quoins at corners .. .. .	S. Ft.	300	
Imitation ashlar facing .. .. .	Sq.	21.00	
Cast iron pipes 4" diameter including hold posts and at every 5 ft. apart .. .. .	R. Ft.	370	

A. S. NAGAVKAR,  
Executive Engineer.